

Addendum

Florida Gateway College
 Building 17 – Anatomy/Physiology Renovations
 Lake City, Florida
 FGC Bid Number: ITB No. 20-3-01

Project

1925

KP Project Number

April 21, 2020

Date

Page 1 of 1

Pages

N/A

Attachments

Five

Addendum Number

This Addendum shall be considered part of the Contract Documents and shall be incorporated integrally into them. Where provisions of the following supplementary data differ from those of the original Contract Documents, this Addendum shall take precedence. Bidders shall acknowledge receipt of this Addendum on their Bid Form.

- ADDENDUM FOUR:** Refer to the reissued Plumbing Sheets. The floor drains indicated as new in the Existing Female and Male Restrooms are not required. The existing floor drains in the existing Restrooms shall remain.

For clarification, the new floor drains in Cadaver Storage 017 and Dissection Room 016 shall be trenched to the tie-in point in the chase wall as shown. All floor slab cutting and patching back to match existing for this work shall be included in the Base Bid. In addition, all chase wall cutting and patching back to match existing for this work shall be included in the Base Bid.

In addition, at the new sinks in Dissection Room 016 all chase wall cutting and patching to match existing for plumbing tie-in shall be included in the Base Bid.

END OF ADDENDUM